


3/4" Ball Valve



Features

- Bi-directional flow
- Makes changing or cleaning sprinklers and spray nozzles easy while system is operating
- Streamlined design reduces snagging and unintentional operation
- Smooth-bore design maximizes flow efficiency
- Quality engineering-grade thermoplastic construction for durability
- UV-resistant, suitable for outdoor installations
- Compact one-piece body design makes it ideal for tight installations
- New design fits into "The One" weight
- Two-year warranty

NOTE: Ball Valves should always be installed upstream of Senninger pressure regulators.



Ball inside valve rotates as knob turns, shutting off the flow of water.



Specifications

- 3/4" F NPT x 3/4" M NPT connections
- 125 psi pressure rating
- Valve length: 2.30"
- Inner diameter: 0.420"
- Part Number: FTV3F3M

